



since 1895  
Lee Walker  
4918 Valley Birch Dr.  
Arlington, TN 38002  
(P) 901-438-2784  
lwalker@garlandind.com

**Millington Central High School**  
**Football Locker Rooms**

**Scope of Work:**

1. Cleaning effectively with blower and push broom to rid the roof of all debris making sure the coating has a clean surface to adhere to.
2. Using Garla Block at a rate of 0.5 gallons per square to prime the roof and allow the coating to adhere better, waiting approx. 25-30 min to allow it to dry to a tackiness before coating the roof.
3. With 9" nap rollers apply White Knight Plus at a rate of 2 gallons per square making sure that walls are coated in a thinner layer and will require three applications. Make sure to use poly scrim in areas that may have holes in the membrane that require reinforcement.

**Material Costs: \$7,766**

**Labor for install provided by Lee Walker/Matthew Campbell with The Garland Co.  
assisting Steve and Melvin the facility managers of the Millington Central H.S.**

*"Service is Our Best Product"*